

1 FORECOURT SITE PLAN - TILE 1

1 : 500




Concrete Flag Paving 600x450mm




Concrete Flag Paving 450x300mm



Concrete Textured Setts 200x200mm




Concrete Deterrent Paving 600x600mm



Planted strips with metal retainer edging

2 FORECOURT SITE PLAN - TILE 2


1 : 500




HARDSCAPING PRODUCT DETAILS

KEY/LOCATION	DESCRIPTION	DIMENSIONS	COLOUR/FINISH	PATTERN
Paving: Western Services Yard and Forecourt pedestrian areas	Concrete Flag Paving - high slip resistance in accordance with BS EN 1339 - chamfered edges	Plan size: 600x450mm Thickness: 80mm	Medium grey	Half staggered joint format
Paving: Western Services Yard and Forecourt pedestrian areas	Concrete Flag Paving - high slip resistance in accordance with BS EN 1339 - chamfered edges	Plan size: 450x300mm Thickness: 80mm	Light grey	Half staggered joint format
Paving: Forecourt pedestrian areas	Concrete Textured Setts - high slip resistance in accordance with BS EN 1339	Plan size: 200x200mm Thickness: 80mm	Anthracite Charcoal	Grid format
Paving: Forecourt areas where pedestrian and vehicle access is discouraged	Concrete Deterrent Paving - Format 3 profile - high slip resistance in accordance with BS EN 1339	Plan size: 600x600mm Thickness: 74mm	White	Grid format
Metal retainers: Western Services Yard and Forecourt landscape planters	Hi-grade bespoke steel panel system - galvanised steel with chamfered edges	Steel panel thickness: 6mm	Galvanised steel	n/a

3 Typical Planter Retainer Wall Detail



4 Typical Pavement Kerb Detail



Note:  
Any reproduction of Ordnance Survey map work illustrated on this drawing is covered by licence (No. SR151580) issued by the Director General, Ordnance Survey and allows Pascal+Watson Limited ("The Licensee") to copy Ordnance Survey material for their business use. The signed control copy of this drawing is held at the offices of Pascal+Watson Limited.

- All information shown outside the Proposal Boundary is for illustrative purposes only.

- Internal layouts are for illustrative purposes only.

- Base building survey information by LCY and MSA

SCALE BAR



C	TM	15.07.22	For Planning Approval
B	RC	20.07.18	For Planning Approval
A	RC	06.10.17	For Planning Approval
Rev	Drn	Date	Description

London City Airport Limited City Aviation House Royal Docks London E16 2pb

**PASCALL +WATSON**

The Warehouses 10 Black Friars Lane London EC4V 6ER  
T +44 (0)20 3837 2500  
[www.pascalls.co.uk](http://www.pascalls.co.uk)

Client

LONDON CITY AIRPORT

Project Name

CITY AIRPORT DEVELOPMENT PROGRAMME

Title

Condition 36

Terminal Forecourt

Indicative Hardscaping Details

Discipline

Architecture

Purpose of Issue

For Approval

Drawing Originator

Pascal+Watson architects

Originators Job No.

5077

Checked By

MN

Checked date

06.10.17

Drawn By

RC

Drawn Date

06.10.17

Approved By

MN

Approval Date

06.10.17

Scale @ A1

As indicated

Building Grid Reference

CADP

Proj Code

Orig

Disc/Zone

Level

Title

Type

Subtype

Dwg Series/NO

Rev

Status

A400PAW

A

14

L00

XXDR

DE735-002

C

S3